# Appendix 5.6

# Modelling Scenarios for Construction Phase



Source ID	Activity	Fine Content	Dry Density (kg/m³)	Production Rate (m³/day)	Spill Rate	Working Hours per day	Sediment Loss Rate (kg/s), see Note 1			
TKO 137 (Figure A5-6-1)										
S1	Sand blanket laying (1 work front)	5%	1,680	1,060	5%	12	0.1031			
	Total 0.103									
TKO 132	(Figures A5-6-2)	-								
D1	Sediment removal (1 work front)	-	-	2,100	20 kg/m <sup>3</sup>	12	0.9722			
S2	Sand blanket laying (seawall) (1 work front)	5%	1,680	1,060	5%	12	0.1031			
S3	Sand blanket laying (reclamation) (1 work front)	5%	1,680	1,060	5%	12	0.1031			
S4	Sand blanket laying (reclamation) (1 work front)	5%	1,680	1,060	5%	12	0.1031			
S5	Sand blanket laying (reclamation) (1 work front)	5%	1,680	1,060	5%	12	0.1031			
D2	Construction of marine viaduct	-	-	18.85 (surface sediment volume disturbed by piling)	20 kg/m <sup>3</sup>	12	0.008727			
						Total	1.393			

### Table A5-6-1 Sediment Loss Rates for Scenario A1 (Unmitigated without Silt Curtain)

Note 1 – The sediment loss rates are rounded up to 4 significant figures.

# Table A5-6-2 Sediment Loss Rates for Scenario A1 (Mitigated with Silt Curtain)

Source ID	Activity	Fine Content	Dry Density (kg/m³)	Production Rate (m³/day)	Spill Rate	Working Hours per day	Layer of Silt Curtains	Sediment Loss Rate (kg/s), see Note 1				
TKO 137 (Figure A5-6-1)												
S1	Sand blanket laying (1 work front)	5%	1,680	1,060	5%	12	Single	0.02576				
							Total	0.02576				
TKO 132 (Figures A5-6-2)												
D1	Sediment removal (1 work front)	-	-	2,100	20 kg/m <sup>3</sup>	12	Double	0.1225				
S2	Sand blanket laying (seawall) (1 work front)	5%	1,680	1,060	5%	12	Double	0.01299				
S3	Sand blanket laying (reclamation) (1 work front)	5%	1,680	1,060	5%	12	Double	0.01299				
S4	Sand blanket laying (reclamation) (1 work front)	5%	1,680	1,060	5%	12	Double	0.01299				
S5	Sand blanket laying (reclamation) (1 work front)	5%	1,680	1,060	5%	12	Double	0.01299				
D2	Construction of marine viaduct	-	-	18.85 (surface sediment volume disturbed by piling)	20 kg/m <sup>3</sup>	12	Single	0.002182				
							Total	0.1766				

Note 1 – The sediment loss rates are rounded up to 4 significant figures.







EIA Report

## Table A5-6-3 Sediment Loss Rates for Scenario A2 (Unmitigated without Silt Curtain)

Source ID	Activity	Fine Content	Dry Density (kg/m³)	Production Rate (m³/day)	Spill Rate	Working Hours per day	Sediment Loss Rate (kg/s), see Note 1			
TKO 137 (Figure A5-6-3)										
S6	Sand blanket laying (1 work front)	5%	1,680	1,060	5%	12	0.1031			
F1	Underwater filling (4 work fronts)	25%	1,900	2,120	5%	12	1.166			
Total							1.269			
TKO 132 (Figures A5-6-4 )										
S7	Sand blanket laying (1 work front)	5%	1,680	1,060	5%	12	0.1031			
S8	Sand blanket laying (1 work front)	5%	1,680	1,060	5%	12	0.1031			
F2	Underwater filling (2 work fronts)	25%	1,900	2,120	5%	12	1.166			
F3	Underwater filling (2 work fronts)	25%	1,900	2,120	5%	12	1.166			
F4	Underwater filling (2 work fronts)	25%	1,900	2,120	5%	12	1.166			
D3	Construction of marine viaduct	-	-	18.85 (surface sediment volume displaced by piling)	20 kg/m <sup>3</sup>	12	0.008727			
						Total	3.713			

Note 1 – The sediment loss rates are rounded up to 4 significant figures.

### Table A5-6-4 Sediment Loss Rates for Scenario A2 (Mitigated with Silt Curtain)

Source ID	Activity	Fine Content	Dry Density (kg/m³)	Production Rate (m³/day)	Spill Rate	Working Hours per day	Layer of Silt Curtains	Sediment Loss Rate (kg/s), see Note 1			
TKO 137 (Figure A5-6-3)											
S6	Sand blanket laying (1 work front)	5%	1,680	1,060	5%	12	Single	0.02576			
F1	Underwater filling (4 work fronts)	25%	1,900	2,120	5%	12	Single	0.2914			
							Total	0.3172			
TKO 132 (Figures A5-6-4 )											
S7	Sand blanket laying (1 work front)	5%	1,680	1,060	5%	12	Double	0.01299			
S8	Sand blanket laying (1 work front)	5%	1,680	1,060	5%	12	Double	0.01299			
F2	Underwater filling (2 work fronts)	25%	1,900	2,120	5%	12	Double	0.1469			
F3	Underwater filling (2 work fronts)	25%	1,900	2,120	5%	12	Double	0.1469			
F4	Underwater filling (2 work fronts)	25%	1,900	2,120	5%	12	Double	0.1469			
D3	Construction of marine viaduct	-	-	18.85 (surface sediment volume displaced by piling)	20 kg/m <sup>3</sup>	12	Single	0.002182			
							Total	0.4689			

Note 1 – The sediment loss rates are rounded up to 4 significant figures.







